

3140 Finley Road
Downers Grove, IL 60515
630.795.3200
Fax 630.795.1130

EPA Region 5 Records Ctr.



July 25, 2003

Mr. Stan Komperda
ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
1021 N. Grand Avenue East
Springfield, IL 62702-4072

Clayton Project 65263.04-007

RE: The Lockformer Company
711 West Ogden Avenue
Lisle, Illinois 60532

Dear Mr. Komperda:

Clayton Group Services, Inc. (Clayton) has prepared the following information package as additional information to support the development of the soil remediation objectives (SROs) for the upper fill/till siltyclay, provided in Section 2.2.1 of the Remedial Action Plan Areas 1 and 2 (*July 2003 Plan*). The information has been prepared on behalf of the Lockformer Company upon the request of the Parson, Inc., oversight consultant for the Illinois EPA.

As presented in Section 2.2.1.2 of the *July 2003 Plan*, SROs were developed for the "Soil Component of the Groundwater Ingestion Route" utilizing "Taco Plus!" software as developed by ATR Associates of Arlington, Virginia. This program was developed to aid in the evaluation of soil and groundwater cleanup levels according to 35 IAC Part 742.

Taco Plus! is capable of providing an array of datasheets to support its various calculations. With respect to the SRO evaluation presented in Section 2.2.1 of the *July 2003 Plan*, datasheets RBCA-V and RBCA-Rf provide the information used to calculate groundwater source (GW_{source}) concentrations and datasheets RBCA-XI and RBCA-XIII provide the information used to calculate Leaching Factor (LF_{sw}) values. SROs were manually calculated using equation R12 in 35 IAC 742, Appendix C, Table C: RBCA Equations (no datasheets provided). In the instance that the calculated GW_{source} concentration exceeded the solubility limit of the chemical in water (S) or the SRO exceeded the soil saturation limit (C_{sat}), Taco Plus! utilized default value equal to the calculated site-specific S and C_{sat} concentrations for each chemical. The S and C_{sat} values are provided in datasheets C and E, respectively. As part of the SRO determination presented in Section 2.2.1 of the *July 2003 Plan*, an evaluation was conducted on each individual zone of impact for each contaminant of concern (COC) (cis-1,2-dichloroethene, trans-1,2-dichloroethene, trichloroethene, tetrachloroethene, 1,1,1-trichloroethane, vinyl chloride, and toluene). The TACO Plus! datasheets containing the support information for each evaluation is presented in Attachments A through F. Each attachment contains the package of datasheets for a specific COC, with the exception of cis-

15-65263ca241

Mr. Stan Komperda
Illinois EPA
Information Package

Clayton Project 15-65263.04.007
July 25, 2003
Page 2

1,2-dichloroethene and trans-1,2-dichloroethene, which were evaluated together due to cumulative effects. Each attachment is further subdivided into the applicable zones of impact (the former fill pipe area, the former vapor degreaser area, and the eastern portion of Area 2).

It is important to note that multiple calculations were required to evaluate the differing lithologies existing at the site (refer to Figure 2.2-9 of the *July 2003 Plan*). Since the soil contamination under evaluation was located in the upper fill/till silty clay, and the aquifer conditions occurred in the underlying mass waste sand and gravel soil, conditions specific to the upper fill/till silty clay were evaluated during the soil calculations, while soil conditions specific to the mass waste sand and gravel were evaluated during the groundwater migration calculations. This resulted in non-applicable being reported in certain datasheets. For example, datasheet RBCA-V provides the information (incorporating soil conditions specific to the mass waste sand and gravel) for the calculation of GW_{source} concentrations. However, TACO Plus! additionally calculates LF_{sw} and SRO values (given the mass waste sand and gravel parameters) and includes these values on datasheet RBCA-V. These values should be disregarded because the appropriate upper fill/till silty clay soil conditions were not considered. (The correct LF_{sw} values are presented on datasheet RBCA-XIII.) Therefore, it is critical to use the datasheets only for the information for which they are provided (detailed above).

Figures 1 through 6 illustrate the contaminant geometry and migration distances used in the GW_{source} calculations. Groundwater flow directions were based on the mass waste unit groundwater level data collected on November 8, 2002. Table 1 provides the individual LF_{sw} values, GW_{source} concentrations, and calculated SROs (using equation R14).

Should you have any questions, do not hesitate to contact the undersigned at 630.795.3206.

Sincerely,



William S. Elwell, P.G.
Senior Project Manager
Environmental Services

cc: Mr. Sasa Jazic, Parsons Inc.
Mr. Om Patel, Weston Solutions
Mr. Howard O. Chinn, Attorney General's Office
Mr. Arthur Bourlard, The Lockformer Company
Mr. Rick Saines, Baker & McKenzie
Mr. Jim Olsen, Tighe & Bond
Mr. Steve Faryan, U.S. EPA

Figures
Tables

Attachment A cis-1,2-Dichloroethene and trans-1,2-Dichloroethene Information
Leaching Factor Datasheets
GW_{source} Datasheets – Former Fill Pipe Area
GW_{source} Datasheets – Area 2
GW_{source} Datasheets – Former Vapor Degreaser Area

Attachment B Tetrachloroethene Information
Leaching Factor Datasheets
GW_{source} Datasheets – Former Fill Pipe Area
GW_{source} Datasheets – Area 2
GW_{source} Datasheets – Former Vapor Degreaser Area


Attachment C Trichloroethene Information
Leaching Factor Datasheets
GW_{source} Datasheets – Former Fill Pipe Area
GW_{source} Datasheets – Area 2
GW_{source} Datasheets – Former Vapor Degreaser Area

Attachment D 1,1,1-Trichloroethane Information
Leaching Factor Datasheets
GW_{source} Datasheets – Northeast Portion of Former Fill Pipe Area
GW_{source} Datasheets – Southwest Portion of Former Fill Pipe Area


Attachment E Vinyl Chloride
Leaching Factor Datasheets
GW_{source} Datasheets – Former Fill Pipe Area
GW_{source} Datasheets – Area 2
GW_{source} Datasheets – Former Vapor Degreaser Area

Attachment F Toluene Information
Leaching Factor Datasheets
GW_{source} Datasheets – Former Fill Pipe Area

FIGURES



CHECK BY	CONTAMINANT TRANSPORT MODEL CIS-1,2-DICHLOROETHENE (CIS-1,2-DCE) & TRANS-1,2-DICHLOROETHENE(T-1,2,-DCE) AREAS 1 & 2 THE LOCKFORMER COMPANY 711 W. OGDEN AVENUE Lisle, ILLINOIS	 FIGURE 1
DRAWN BY BCP		
DATE 7-23-03		
SCALE AS SHOWN		
CAD NO. 6526316Z		
PRJ NO. 65263.16		




CHECK BY	
DRAWN BY	BCP
DATE	7-23-03
SCALE	AS SHOWN
CAD NO.	6526316Z
PRJ NO.	65263.16

CONTAMINANT TRANSPORT MODEL
TETRACHLOROETHANE (PCE)
AREAS 1 & 2
THE LOCKFORMER COMPANY
711 W. OGDEN AVENUE
LISLE, ILLINOIS



FIGURE

2




CHECK BY	
DRAWN BY BCP	
DATE	7-23-03
SCALE	AS SHOWN
CAD NO.	6526316Z
PRJ NO.	65263.16

CONTAMINANT TRANSPORT MODEL
TRICHLOROETHANE (TCE)
AREAS 1 & 2
THE LOCKFORMER COMPANY
711 W. OGDEN AVENUE
LISLE, ILLINOIS



FIGURE

3




CHECK BY	
DRAWN BY	BCP
DATE	7-23-03
SCALE	AS SHOWN
CAD NO.	6526316Z
PRJ NO.	65263.16

CONTAMINANT TRANSPORT MODEL
1,1,1-TRICHLOROETHANE (1,1,1-TCA)
AREAS 1 & 2
THE LOCKFORMER COMPANY
711 W. OGDEN AVENUE
LISLE, ILLINOIS



FIGURE

4




CHECK BY	
DRAWN BY	BCP
DATE	7-23-03
SCALE	AS SHOWN
CAD NO.	6526316Z
PRJ NO.	65263.16

CONTAMINANT TRANSPORT MODEL
VINYL CHLORIDE (VC)
AREAS 1 & 2
THE LOCKFORMER COMPANY
711 W. OGDEN AVENUE
LISLE, ILLINOIS



FIGURE 5



CHECK BY	
DRAWN BY BCP	
DATE	7-23-03
SCALE	AS SHOWN
CAD NO.	6526316Z
PRJ NO.	65263.16

CONTAMINANT TRANSPORT MODEL
TOLUENE
AREAS 1 & 2
THE LOCKFORMER COMPANY
711 W. OGDEN AVENUE
LISLE, ILLINOIS



TABLES

TABLE 1
Soil Remediation Objective Table
Upper Till/Fill in Areas 1 and 2

The Lockformer Company / Lisle, Illinois

Compound of Concern		Leaching Factor (LF_{sw}) ($\frac{mg/l}{mg/kg}$)	GW_{source} (mg/L)	^a Calculated SRO (mg/kg) (GW_{source}/LF_{sw})
cis-1,2-Dichloroethene		0.11		
	Former Fill Pipe Area		19.4	176.364
	Area 2		1.13	10.273
	Former Vapor Degreaser Area		3.07	27.909
trans-1,2-Dichloroethene		0.0864		
	Former Fill Pipe Area		60.3	697.917
	Former Vapor Degreaser Area		6.98	80.787
Tetrachloroethene		0.0384		
	Former Fill Pipe Area		^b 200	^c 260
	Area 2		^b 200	^c 260
	Former Vapor Degreaser Area		^b 200	^c 260
Trichloroethene		0.0364		
	Former Fill Pipe Area		^b 1100	^c 1510
	Area 2		13	357
	Former Vapor Degreaser Area		43.6	1,197
1,1,1-Trichloroethane		0.0507		
	Former Fill Pipe Area (NE)		^b 1330	^c 1310
	Former Fill Pipe Area (SW)		^b 1330	^c 1310
Vinyl Chloride		0.142		
	Former Fill Pipe Area		0.201	1.415
	Area 2		0.0156	0.11
	Former Vapor Degreaser Area		0.0277	0.195
Toluene		0.0337		
	Former Fill Pipe Area		^b 526	^c 780

NOTES:

^a Using 35 IAC 742, Appendix C, Table C: Equation R12.

^b Default value equal to the compound specific solubility limit.

^c Default value equal to the compound specific soil saturation limit.

SRO = Soil Remediation Objective (soil component of the groundwater ingestion route)

GW_{source} = Groundwater Concentration at the Source

ATTACHMENT A

**CIS-1,2-DICHLOROETHENE AND TRANS-1,2-DICHLOROETHENE
INFORMATION**

CIS-1,2-DCE AND TRANS-1,2-DCE

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LFsw

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.72
H' (unitless)***	See below	θ_{ws} (unitless)**	0.35
U_{gw} (cm/yr)****	229.90	θ_{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ_{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	7 925		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

Chemical Properties (see Datasheet C) * U_{gw} value as calculated using Equation R24

Chemical Name	k_s (gwater/gsoil)	H' (unitless)	LFsw (mg/Lwater)/(mg/kgsoil)
Dichloroethylene, cis-1,2-	0.2485	1.67E-001	1.10E-01
Dichloroethylene, trans-1,2-	0.3675	3.85E-001	8.64E-02

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ^l /g)	foc** (g/g)	ks (g/g soil)/(g/cm ^l water)	pH	Koc* (cm ^l /g)	foc** (g/g)	ks (g/g soil)/(g/cm ^l water)
Dichloroethylene, cis-1,2-	0.00	3.55E+001	0.000	0.21300	6.80	3.55E+001	0.007	0.24850
Dichloroethylene, trans-1,2-	0.00	5.25E+001	0.000	0.31500	6.80	5.25E+001	0.007	0.36750

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

CIS-1,2-DCE AND TRANS-1,2-DCE

**GW_{source} DATASHEETS
FORMER FILL PIPE AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	18,898.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	1,890
GW _{comp} (mg/L)**	See below	α_y (cm)	630
C(x)/C _{source} (unitless)***	See below	α_z (cm)	94
U (cm/d)	1.6600	S _w (cm)	2,743
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.38		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Dichloroethylene, cis-1,2-	19.4262	6.46E-01	0.07	3.60E-03	0.000240	30.088
Dichloroethylene, trans-1,	60.3052	5.09E-01	0.1	1.66E-03	0.000240	118.438

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	630
X (cm)	18,898.00	S _d (cm)	200
α_x (cm)*	1,890	α_z (cm)	94
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	1.66	i (unitless)	0.003
Sw (cm)	2,743	θ_T (unitless)**	0.38

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Dichloroethylene, cis-1,2-	0.0002400		
Dichloroethylene, trans-1,2-	0.0002400		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.72
K_{oc} (gwater/gsoil)*	See below	f_{oc} (unitless)**	0.007
n Total Porosity**	0.38		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Dichloroethylene, cis-1,2-	35.50	0.2485	2.13
Dichloroethylene, trans-1,2-	52.50	0.3675	2.67

CIS-1,2-DCE

GW_{source} DATASHEETS
AREA 2

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	7,163.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	αx (cm)	716
GW _{comp} (mg/L)**	See below	αy (cm)	239
C(x)/C _{source} (unitless)***	See below	αz (cm)	36
U (cm/d)	2.2500	S _w (cm)	1,981
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Dichloroethylene, cis-1,2-	1.1276	6.35E-01	0.07	6.21E-02	0.000240	1.775

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	239
X (cm)	7,163.00	S _d (cm)	200
α_x (cm)*	716	α_z (cm)	36
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
S _w (cm)	1,981	θ_T (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Dichloroethylene, cis-1,2-	0.0002400		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L water)/(mg/kg soil)
Dichloroethylene, cis-1,2-	35.50	0.2840	2.93

CIS-1,2-DCE AND TRANS-1,2-DCE

**GW_{source} DATASHEETS
FORMER VAPOR DEGREASER AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	8,839.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	884
GW _{comp} (mg/L)**	See below	α_y (cm)	295
C(x)/C _{source} (unitless)***	See below	α_z (cm)	44
U (cm/d)	1.6600	S _w (cm)	1,219
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.38		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Dichloroethylene, cis-1,2-	3.0740	3.43E-01	0.07	2.28E-02	0.000240	8.960
Dichloroethylene, trans-1,	6.9760	2.71E-01	0.1	1.43E-02	0.000240	25.784

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	295
X (cm)	8,839.00	S _d (cm)	200
α_x (cm)*	884	α_z (cm)	44
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	1.66	i (unitless)	0.003
S _w (cm)	1,219	θT (unitless)**	0.38

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Dichloroethylene, cis-1,2-	0.0002400		
Dichloroethylene, trans-1,2-	0.0002400		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.72
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.007
n Total Porosity**	0.38		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L _{water})/(mg/kgsoil)
Dichloroethylene, cis-1,2-	35.50	0.2485	2.13
Dichloroethylene, trans-1,2-	52.50	0.3675	2.67

ATTACHMENT B

TETRACHLOROETHENE INFORMATION

TETRACHLOROETHENE

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LFsw

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.72
H' (unitless)***	See below	θ_{ws} (unitless)**	0.35
U_{gw} (cm/yr)****	229.90	θ_{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ_{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	777		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C) **** U_{gw} value as calculated using Equation R24

Chemical Name	k_s (gwater/gsoil)	H' (unitless)	LFsw (mg/Lwater)/(mg/kgsoil)
Tetrachloroethylene	1.0850	7.54E-001	3.84E-02

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)
Tetrachloroethylene	6.80	1.55E+002	0.006	0.93000	6.80	1.55E+002	0.007	1.08500

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

Datasheet E: Soil Saturation Limits

Chemical	Constituent Properties					Saturation Limits	
	Solubility mg/L	Kd (Surface) cm ³ /g	Kd (Subsurface) cm ³ /g	Henry's Law Constant (H') (dimensionless)	Organic Carbon Partition Coefficient (Koc)	Csat (Surface Soils) mg/kg	Csat (Subsurface Soils) mg/kg
Tetrachloroethylene	2.00E+002	0.930	1.085	7.54E-001	1.55E+002	234.15	260.33

TETRACHLOROETHENE

**GW_{source} DATASHEETS
FORMER FILL PIPE AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	18,898.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	1,890
GW _{comp} (mg/L)**	See below	α_y (cm)	630
C(x)/C _{source} (unitless)***	See below	α_z (cm)	94
U (cm/d)	2.2500	S _w (cm)	1,981
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Tetrachloroethylene	200.000	1.69E-01	0.005	1.65E-11	0.000960	273.538

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	630
X (cm)	18,898.00	S _d (cm)	200
α_x (cm)*	1,890	α_z (cm)	94
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,981	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C _(x) (mg/L)
Tetrachloroethylene	0.0009600		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.90
Koc (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	Koc - Subsurface (gwater/gsoil)	ks (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Tetrachloroethylene	155.00	1.2400	9.41

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Tetrachloroethylene	2.00E+002	7.20E-002	8.20E-006	7.54E-001	1.55E+002	0.000960

TETRACHLOROETHENE

GW_{source} DATASHEETS
AREA 2

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	7,315.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	αx (cm)	732
GW _{comp} (mg/L)**	See below	αy (cm)	244
C(x)/C _{source} (unitless)***	See below	αz (cm)	37
U (cm/d)	2.2500	S _w (cm)	1,676
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Tetrachloroethylene	200.000	1.49E-01	0.005	8.95E-07	0.000960	273.538

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

Csource (mg/L)	See below	α_y (cm)	244
X (cm)	7,315.00	Sd (cm)	200
α_x (cm)*	732	α_z (cm)	37
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,676	θ_T (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	Csource* (mg/L)	C(x) (mg/L)
Tetrachloroethylene	0.0009600	0.00000	0.00E+00

* Note: Csource is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Tetrachloroethylene	155.00	1.2400	9.41

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Tetrachloroethylene	2.00E+002	7.20E-002	8.20E-006	7.54E-001	1.55E+002	0.000960

TETRACHLOROETHENE

GW_{source} DATASHEETS
FORMER VAPOR DEGREASER AREA

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	8,992.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	899
GW _{comp} (mg/L)**	See below	α_y (cm)	300
C(x)/C _{source} (unitless)***	See below	α_z (cm)	45
U (cm/d)	2.2500	S _w (cm)	1,067
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Tetrachloroethylene	200.000	1.02E-01	0.005	7.88E-08	0.000960	273.538

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	300
X (cm)	8,992.00	S _d (cm)	200
α_x (cm)*	899	α_z (cm)	45
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,067	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Tetrachloroethylene	0.0009600	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Tetrachloroethylene	155.00	1.2400	9.41

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Tetrachloroethylene	2.00E+002	7.20E-002	8.20E-006	7.54E-001	1.55E+002	0.000960

ATTACHMENT C

TRICHLOROETHENE INFORMATION

TRICHLOROETHENE

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LF_{sw}

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.72
H' (unitless)***	See below	θ _{ws} (unitless)**	0.35
U _{gw} (cm/yr)****	229.90	θ _{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ _{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	9 144		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

Chemical Properties (see Datasheet C) * U_{gw} value as calculated using Equation R24

Chemical Name	ks (gwater/gsoil)	H' (unitless)	LF _{sw} (mg/L _{water})/(mg/kgsoil)
Trichloroethylene	1.1620	4.22E-001	3.64E-02

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ² /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)	pH	Koc* (cm ² /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)
Trichloroethylene	6.80	1.66E+002	0.006	0.99600	6.80	1.66E+002	0.007	1.16200

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

Datasheet E: Soil Saturation Limits

Chemical	Constituent Properties					Saturation Limits	
	Solubility mg/L	Kd (Surface) cm ³ /g	Kd (Subsurface) cm ³ /g	Henry's Law Constant (H') (dimensionless)	Organic Carbon Partition Coefficient (Koc)	Csat (Surface Soils) mg/kg	Csat (Subsurface Soils) mg/kg
Trichloroethylene	1.10E+003	0.996	1.162	4.22E-001	1.66E+002	1,292.25	1,510.97

TRICHLOROETHENE

**GW_{source} DATASHEETS
FORMER FILL PIPE AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	18,593.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	1,859
GW _{comp} (mg/L)**	See below	α_y (cm)	620
C(x)/C _{source} (unitless)***	See below	α_z (cm)	93
U (cm/d)	2.2500	S _w (cm)	3,505
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Trichloroethylene	1100.000	3.51E-02	0.005	1.76E-07	0.000420	1573.109

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	620
X (cm)	18,593.00	S _d (cm)	200
α_x (cm)*	1,859	α_z (cm)	93
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	3,505	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Trichloroethylene	0.0004200		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	f_{oc} (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	R_f (mg/Lwater)/(mg/kgsoil)
Trichloroethylene	166.00	1.3280	10.01

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Trichloroethylene	1.10E+003	7.90E-002	9.10E-006	4.22E-001	1.66E+002	0.000420

TRICHLOROETHENE

GW_{source} DATASHEETS
AREA 2

SOUTHWEST PORTION OF FORMER FILL PIPE AREA

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	7,071.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	707
GW _{comp} (mg/L)**	See below	α_y (cm)	236
C(x)/C _{source} (unitless)***	See below	α_z (cm)	35
U (cm/d)	2.2500	S _w (cm)	3,962
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Trichloroethylene	12.9739	2.63E-01	0.005	3.85E-04	0.000420	49.280

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	236
X (cm)	7,071.00	S _d (cm)	200
α_x (cm)*	707	α_z (cm)	35
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	3,962	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Trichloroethylene	0.0004200	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L _{water})/(mg/kgsoil)
Trichloroethylene	166.00	1.3280	10.01

TRICHLOROETHENE

**GW_{source} DATASHEETS
FORMER VAPOR DEGREASER AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	8,534.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	853
GW _{comp} (mg/L)**	See below	α_y (cm)	284
C(x)/C _{source} (unitless)***	See below	α_z (cm)	43
U (cm/d)	2.2500	S _w (cm)	3,810
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Trichloroethylene	43.5543	2.57E-01	0.005	1.15E-04	0.000420	169.555

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	284
X (cm)	8,534.00	S _d (cm)	200
α_x (cm)*	853	α_z (cm)	43
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	3,810	θ_T (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Trichloroethylene	0.0004200	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	f_{oc} (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	R_f (mg/L water)/(mg/kg soil)
Trichloroethylene	166.00	1.3280	10.01

ATTACHMENT D

1,1,1-TRICHLOROETHANE INFORMATION

1,1,1-TCA

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LFsw

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

ks (gwater/gsoil)*	See below	ρs (g/cm ³)**	1.72
H' (unitless)***	See below	θ _{ws} (unitless)**	0.35
U _{gw} (cm/yr)****	229.90	θ _{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ _{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	1 676		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

Chemical Properties (see Datasheet C) * U_{gw} value as calculated using Equation R24

Chemical Name	ks (gwater/gsoil)	H' (unitless)	LF _{sw} (mg/L _{water})/(mg/kgsoil)
Trichloroethane, 1,1,1-	0.7700	7.05E-001	5.07E-02

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)
Trichloroethane, 1,1,1-	6.80	1.10E+002	0.006	0.66000	6.80	1.10E+002	0.007	0.77000

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

Datasheet E: Soil Saturation Limits

Chemical	Constituent Properties					Saturation Limits	
	Solubility mg/L	Kd (Surface) cm ³ /g	Kd (Subsurface) cm ³ /g	Henry's Law Constant (H') (dimensionless)	Organic Carbon Partition Coefficient (K _{oc})	Csat (Surface Soils) mg/kg	Csat (Subsurface Soils) mg/kg
Trichloroethane, 1,1,1-	1.33E+003	0.660	0.770	7.05E-001	1.10E+002	1,185.83	1,311.23

1,1,1-TCA

GW_{source} DATASHEETS
NORTHEAST PORTION OF FORMER FILL PIPE AREA

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	24,384.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	2,438
GW _{comp} (mg/L)**	See below	α_y (cm)	813
C(x)/C _{source} (unitless)***	See below	α_z (cm)	122
U (cm/d)	2.2500	S _w (cm)	1,372
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θ_T (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Trichloroethane, 1,1,1-	1330.000	1.72E-01	0.2	2.12E-13	0.001300	1335.012

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	813
X (cm)	24,384.00	S _d (cm)	200
α_x (cm)*	2,438	α_z (cm)	122
λ (1/day)**	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,372	θ_T (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Trichloroethane, 1,1,1-	0.0013000	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.90
Koc (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	Koc - Subsurface (gwater/gsoil)	ks (gwater/gsoil)	Rf (mg/L water)/(mg/kg soil)
Trichloroethane, 1,1,1-	110.00	0.8800	6.97

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Trichloroethane, 1,1,1-	1.33E+003	7.80E-002	8.80E-006	7.05E-001	1.10E+002	0.001300

1,1,1-TCA

GW_{source} DATASHEETS
SOUTHWEST PORTION OF FORMER FILL PIPE AREA

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	18,898.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	αx (cm)	1,890
GW _{comp} (mg/L)**	See below	αy (cm)	630
C(x)/C _{source} (unitless)***	See below	αz (cm)	94
U (cm/d)	2.2500	S _w (cm)	1,067
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm/cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Trichloroethane, 1,1,1-	1330.000	1.39E-01	0.2	8.59E-12	0.001300	1335.012

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	630
X (cm)	18,898.00	S _d (cm)	200
α_x (cm)*	1,890	α_z (cm)	94
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,067	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C _(x) (mg/L)
Trichloroethane, 1,1,1-	0.0013000	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	R_f (mg/L water)/(mg/kgsoil)
Trichloroethane, 1,1,1-	110.00	0.8800	6.97

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Trichloroethane, 1,1,1-	1.33E+003	7.80E-002	8.80E-006	7.05E-001	1.10E+002	0.001300

ATTACHMENT E

VINYL CHLORIDE

VINYL CHLORIDE

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LFsw

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.72
H' (unitless)***	See below	θ _{ws} (unitless)**	0.35
U _{gw} (cm/yr)****	229.90	θ _{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ _{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	8 077		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

Chemical Properties (see Datasheet C) * U_{gw} value as calculated using Equation R24

Chemical Name	ks (gwater/gsoil)	H' (unitless)	LFsw (mg/L _{water})/(mg/kgsoil)
Vinyl chloride	0.1302	1.11E+000	1.42E-01

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)
Vinyl chloride	6.80	1.86E+001	0.006	0.11160	6.80	1.86E+001	0.007	0.13020

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

VINYL CHLORIDE

**GW_{source} DATASHEETS
FORMER FILL PIPE AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	19,506.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	1,951
GW _{comp} (mg/L)**	See below	α_y (cm)	650
C(x)/C _{source} (unitless)***	See below	α_z (cm)	98
U (cm/d)	2.2500	S _w (cm)	3,048
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datasheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Vinyl chloride	0.2010	1.63E-01	0.002	9.95E-03	0.000240	1.230

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	650
X (cm)	19,506.00	S _d (cm)	200
α_x (cm)*	1,951	α_z (cm)	98
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	3,048	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Vinyl chloride	0.0002400		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	f_{oc} (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	R_f (mg/L water)/(mg/kgsoil)
Vinyl chloride	18.60	0.1488	2.01

VINYL CHLORIDE

**GW_{source} DATASHEETS
AREA 2**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this datasheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	7,315.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	αx (cm)	732
GW _{comp} (mg/L)**	See below	αy (cm)	244
C(x)/C _{source} (unitless)***	See below	αz (cm)	37
U (cm/d)	2.2500	S _w (cm)	2,591
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Vinyl chloride	0.0156	1.63E-01	0.002	1.28E-01	0.000240	0.096

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	244
X (cm)	7,315.00	S _d (cm)	200
α_x (cm)*	732	α_z (cm)	37
λ (1/day)**	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	2,591	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Vinyl chloride	0.0002400		

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.90
Koc (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	Koc - Subsurface (gwater/gsoil)	ks (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Vinyl chloride	18.60	0.1488	2.01

VINYL CHLORIDE

**GW_{source} DATASHEETS
FORMER VAPOR DEGREASER AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	8,230.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	823
GW _{comp} (mg/L)**	See below	α_y (cm)	274
C(x)/C _{source} (unitless)***	See below	α_z (cm)	41
U (cm/d)	2.2500	S _w (cm)	1,829
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Vinyl chloride	0.0277	1.63E-01	0.002	7.21E-02	0.000240	0.170

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	274
X (cm)	8,230.00	S _d (cm)	200
α_x (cm)*	823	α_z (cm)	41
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,829	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C(x) (mg/L)
Vinyl chloride	0.0002400	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	f_{oc} (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	R_f (mg/L water)/(mg/kgsoil)
Vinyl chloride	18.60	0.1488	2.01

ATTACHMENT F

TOLUENE INFORMATION

TOLUENE

LEACHING FACTOR DATASHEETS

Datasheet RBCA-XIII. LFsw

Datasheet RBCA-XIII is to be used to propose the leaching factor calculated by the equation in Appendix C, Table C of TACO: Equation R14 (residential, industrial/commercial and construction worker scenarios). The use of Equations R20 and R24 in TACO are necessary to generate some of the input values for Equation R14. Since the values in Datasheet RBCA-XI are used in this evaluation, this Datasheet must also be submitted.

ks (gwater/gsoil)*	See below	ps (g/cm ³)**	1.72
H' (unitless)***	See below	θ _{ws} (unitless)**	0.35
U _{gw} (cm/yr)****	229.90	θ _{as} (unitless)**	0.03
K (cm/yr)	76,632.00		
i (unitless)	0.003		
δ _{gw} (cm)	200		
I (cm/yr)	7		
W (cm)	1 524		

* ks value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

Chemical Properties (see Datasheet C) * U_{gw} value as calculated using Equation R24

Chemical Name	ks (gwater/gsoil)	H' (unitless)	LFsw (mg/Lwater)/(mg/kgsoil)
Toluene	1.2740	2.72E-001	3.37E-02

Datasheet RBCA-XI. ks

Datasheet RBCA-XI is to be used to propose the soil water sorption coefficient (ks) calculated by the equation in Appendix C, Table C of TACO: Equation R20 (residential, industrial/commercial and construction worker scenarios).

Land Use Scenario: **Residential, Industrial/Commercial and Construction Worker**

Chemical Name	Surface Soils				Subsurface Soils			
	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)	pH	Koc* (cm ³ /g)	foc** (g/g)	ks (g/g soil)/(g/cm ³ water)
Toluene	6.80	1.82E+002	0.006	1.09200	6.80	1.82E+002	0.007	1.27400

* Chemical Properties (see Datasheet C)

** Physical Soil Parameters (see Datasheet B)

Datasheet E: Soil Saturation Limits

Chemical	Constituent Properties					Saturation Limits	
	Solubility mg/L	Kd (Surface) cm ³ /g	Kd (Subsurface) cm ³ /g	Henry's Law Constant (H') (dimensionless)	Organic Carbon Partition Coefficient (K _{oc})	Csat (Surface Soils) mg/kg	Csat (Subsurface Soils) mg/kg
Toluene	5.26E+002	1.092	1.274	2.72E-001	1.82E+002	653.70	780.24

TOLUENE

**GW_{source} DATASHEETS
FORMER FILL PIPE AREA**

Datasheet RBCA-V. Migration to Ground Water - Class 1

Datasheet RBCA-V is to be used to propose soil cleanup objectives for the migration to ground water exposure route calculated by the equation in Appendix C, Table C of TACO: Equation R12 (residential, industrial/commercial and construction worker scenarios). Equations described under RBCA-VI and RBCA-VIII as well as the equations in 35 Ill. Adm. Code 620, Subpart F may also be required to generate some of the input values for equation R12. Note; use 35 Ill. Code 620, Subpart F to calculate cleanup objectives for noncarcinogens. Since values listed in RBCA-XIII are used in this evaluation, this dataheet must be submitted. In cases where the target cancer risk (TR) exceeds 1 in 1,000,000, Datasheet -VI must also be submitted.

Land Use Scenario: **ALL**

Institutional Control YES NO
Engineered Barrier YES NO

GW _{source} (mg/L)	See below	X (cm)	18,593.00
LF _{sw} [(mg/L)/(mg/kg)]*	See below	α_x (cm)	1,859
GW _{comp} (mg/L)**	See below	α_y (cm)	620
C(x)/C _{source} (unitless)***	See below	α_z (cm)	93
U (cm/d)	2.2500	S _w (cm)	1,128
K (cm/d)	209.951	λ (1/d)****	See below
i (cm/cm)	0.0030	S _d (cm)	200
θT (cm ³ /cm ³ -soil)*****	0.28		

* LF_{sw} reported on Datasheet RBCA-XIII

** GW_{comp} reported on Datasheet RBCA-VI

*** C(x)/C_{source} reported on Datsheet RBCA-VI

**** Chemical Parameters (see Datasheet C)

***** Physical Soil Parameters (see Datasheet B)

Chemical Name	GW _{source} (mg/L)	LF _{sw} (mg/L)/(mg/kg)	GW _{comp} (mg/L)	C(x)/C _{source} (unitless)	λ (1/day)	Soil Cleanup Objective (mg/kg)
Toluene	526.000	9.49E-02	1	7.91E-43	0.011000	812.738

Datasheet RBCA-VII. Concentration of Contaminant in Groundwater Source

Datasheet RBCA-VII is to be used to predict the groundwater concentration at a specified distance from the source as calculated by the equation in Appendix C of TACO: Equation R26 (residential, industrial/ commercial and construction worker scenarios). Since values listed in Datasheet RBCA-V are used in this evaluation, this datasheet must also be submitted.

C _{source} (mg/L)	See below	α_y (cm)	620
X (cm)	18,593.00	S _d (cm)	200
α_x (cm)*	1,859	α_z (cm)	93
λ (1/day)***	See below	K (cm/d)	209.95
U (cm/d)*	2.25	i (unitless)	0.003
Sw (cm)	1,128	θT (unitless)**	0.28

* α_x , α_y , α_z , and U are reported on Datasheet RBCA-V ** Physical Soil Parameter (see Datasheet B)

*** Chemical Properties (see Datasheet C)

Chemical Name	λ (1/day)	C _{source} * (mg/L)	C _(x) (mg/L)
Toluene	0.0110000	0.00000	0.00E+00

* Note: C_{source} is the measured concentration at the source for this form.

Datasheet C: Chemical Properties

Chemical	Solubility in Water (S) (mg/L)	Diffusivity in Air (Di) (cm ² /s)	Diffusivity in Water (Dw) (cm ² /s)	Henry's Law Constant (H' @ 25°C)	Organic Carbon Partition Coefficient (Koc - L/kg)	First Order Decay Constant (λ - 1/day)
Toluene	5.26E+002	8.70E-002	8.60E-006	2.72E-001	1.82E+002	0.011000

Datasheet Rf - RBCA Retardation Factors

Datasheet Rf - RBCA Retardation Factors presents the information used to calculate the retardation factors used in RBCA Equations R15 and R26. The Retardation Factors are used to modify the Specific Discharge to better represent the rate at which the contaminant moves through the saturated zone. For further information see: Domenico, P.A. and F. W. Schwartz. "Physical and Chemical Hydrogeology". 2nd Edition. John Wiley & Sons. New York. pg. 377.

k_s (gwater/gsoil)*	See below	ρ_s (g/cm ³)**	1.90
K_{oc} (gwater/gsoil)*	See below	foc (unitless)**	0.008
n Total Porosity**	0.28		

* k_s value reported on Datasheet RBCA-XI

** Physical Soil Properties (see Datasheet B)

***Chemical Properties (see Datasheet C)

Chemical Name	K_{oc} - Subsurface (gwater/gsoil)	k_s (gwater/gsoil)	Rf (mg/L water)/(mg/kgsoil)
Toluene	182.00	1.4560	10.88